

# GH ACTIONS - ANSIBLE


Task – limplementing a Deployment Pipeline, using ansible and GitHub Actions for invocation.

All codes are stored in own public GitHub repository




Actions-Ansible.

Below, provided overview of current working tree in GitHub:



### ANSIBLE – WORKING TREE

In ansible working directory consist of next: roles, configuration files (ansible.cfg), inventory file (inventory) and ansible-playbook itself calling python.yml



name: Installing Python Environment
 hosts: developers
 become: true
 roles:
 - python\_dev

### Ansible playbook:

- playbook will be run on a group of hosts with name developers;
- running tasks in privilege mode;
- roles to be started python\_dev.

```
1 [defaults]
2 host_key_checking = false
3 inventory = inventory
4 roles_path = $HOME/$USER/ghActions-Ansible/ansible/roles
```

### In ansible.cfg as a default were defined:

- host\_key\_checking to avoiding prompt key confirmation
- path to inventory file
- and path for roles location

```
1 [developers]
2 localhost ansible_connection=local
```

#### **Inventory**:

 given a name of host (localhost) and connection type (otherwise used IP address or DNS name)

## ANSIBLE - ROLES

loop control:

label: "{{ item | basename | splitext | first }}"

Ansible roles structure have been generated by using ansible-galaxy. For that project, its enough to have only 3 directories names: files, tasks and vars.



## GH ACTIONS - WORKFLOW

```
name: Ansible
  push:
   branches:
   - main
 workflow dispatch:
jobs:
  validate:
   runs-on: ubuntu-latest
   steps:
     - uses: actions/checkout@v3.0.0
     - name: Run ansible-lint
       uses: ansible-community/ansible-lint-action@v6.0.2
       with:
         args: "ansible"
  deployAnsible:
   runs-on: ubuntu-latest
   needs: [validate]
   steps:
     - uses: actions/checkout@v3.0.0
     - name: Run Ansible playbook
       uses: dawidd6/action-ansible-playbook@v2.5.0
       with:
         playbook: python.yml
         directory: ansible
     - name: Checking adjusted Python venvs
       run: ls -la "/opt/python_venvs/"
```



Creating of pipeline begin with name assignment of the workflow and defining event that triggers of the workflow. In our case - on push (main branch) and manually.

First job naming - <u>validate</u>, performing checking for a quality and respectability to a proven practices of an ansible files.

As a runner - using GH Actions runner.

Linux - Ubuntu.


Before start to run ansbile-lint from marketplace, need to checkout repository to GH runner.


Second job naming - <u>deployAnsbile</u>, responsible for running ansible playbook. But, first of all it would start only if previous job "validate" finished successfully.

After that, deployment of ansible-playbook using special tool from GH marketplace. Finally, verification if python-vevns installed

configured properly.

### GH ACTIONS - PIPELINE OVERVIEW





- 1. Overall view to GHA pipeline.
- 2. Examining by ansible-lint ansbile ".yml" files.
- 3. Run playbook.
- 4. Checking presence of python\_venvs in mentioned path.

```
/opt/pipx_bin/ansible-playbook python.yml
  10 ok: [localhost]
  changed: [localhost]
  changed: [localhost]
  TASK [python dev : Install Python venvs from requirements.txt] *****************
  changed: [localhost] => (item=requirements10)
  changed: [localhost] => (item=requirements1)
                          changed=3
                                   unreachable=0
                                              failed=0
```

```
1  ▶ Run 1s -la "/opt/python_venvs/"
4  total 16
5  drwxrwxrwx+ 4 root root 4096 Sep 7 15:58 .
6  drwxrwxrwx+ 16 root root 4096 Sep 7 15:57 ..
7  drwxrwxrwx+ 6 root root 4096 Sep 7 15:58 requirements1
8  drwxrwxrwx+ 6 root root 4096 Sep 7 15:57 requirements10
```